# BRUHATH BENGALURU MAHANAGARA PALIKE

**Yelahanka Division, Yelahanka Zone**

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

## APPROVED TENDER SCHEDULE –'B'

Item No: 74

Name of Work:-Asphalting to cross roads from 2 to 6 and drains in Mathrulayout in ward no:04

| Sl | Description | Uni. | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri.THILAK KUMAR H S | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no138,PWD SR 2014-15) | Cum | 34.88 | 74.80 | Rupees seventy four and paise eighty only |
| 2 | KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15 | Cum | 73.80 | 261.90 | Rupees two thousand sixty one and paise ninety only |
| 3 | KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.83cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no4.3,Page no12,PWD SR 2014-15) | Cum | 11.03 | 4798.56 | Rupees four thousand seven hundred ninety eight and paise fifty six only |
| 4 | KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work(pwd sr2014-15,p.no13,sno4.11) | Cum | 58.29 | 6004.60 | Rupees six thousand four and paise sixty only |

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri.THILAK KUMAR H S | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 5 | KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe550(pwd sr2014-15,p.no17,s.no4.46) | Qnt | 79.9[illegible] | 7826.54 | Rupees seven thousand eight hundred twenty six and paise fifty four only |
| 6 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecification. Specification no.KBS 4.6.2(pwd sr2014-15,p.no15/4.31) | Sqm | 211.6[illegible] | 289.75 | Rupees two hundred eighty nine and paise seventy five only |
| 7 | KSRRB M400-17: Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification: | Cum | 53.88 | 1424.17 | Rupees one thousand four hundred twenty four and paise seventeen only |
| 8 | KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH SpecificationsNo502 (ITEMNO21.6,Page no157,PWD SR 2014-15) | Sqm | 990.00 | 34.84 | Rupees thirty four and paise eighty four only |
| 9 | KSRRB M500-18.Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler,transporting the hot mix to work site.laying with a paver finisher to the required grade,levell and gnment,rollingwithsmoothwheeled,vibratoryandtandemrollers to achievethedesiredcompactionasperMORTHSpecificationclausno508completeinallrespectscompiet asperspecifications.using100120THcapacityH.M.P with sensor paver gradingl(35-40mm)with4.5%CRMB55grade(Itemno21.21.1,Pageno16D 2014-15) | Cum | 24.7[illegible] | 10093.20 | Rupees ten thousand ninety three and paise twenty only |
| 10 | KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15) | Cum | 108.68 | 67.35 | Rupees sixty seven and paise thirty five only |

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.